



Palm Beach County Fire Rescue Community Risk Reduction Division is very supportive prior to issuing a Temporary Certificate of Occupancy allowing buildings near completion to be occupied by construction staff (removal of trailer), the stocking of furniture, equipment and supplies, and/or allowing the owner or their representative(s) to begin training their staff within the facility provided ALL the following conditions are met.

- 1. A Temporary Certificate of Occupancy "TCO" permit is applied and paid for
- 2. The Fire Sprinkler System is 100% Complete (all ceiling tiles must be in place)
- 3. The Fire Alarm System is 100% Complete with the Monitoring and Maintenance Contracts Established
- 4. If required, the "BDA" System is 100% Complete
- 5. All required documentation for the Fire Sprinkler and Fire Alarm has been received
- 6. The Access Box (Knox Box) is properly installed, and all required keys are placed in the box
- 7. The Elevators must pass the State of Florida Inspection (elevator recall is part of the Fire Alarm inspection)
- 8. No exposed wiring
- 9. The Owner, their Representatives and Staff shall not be allowed in any areas that may subject them to a high risk of injury or death (example electrical / mechanical rooms)

Upon passing the "TCO", the Fire Marshal's office will notify you of the conditions allowed based on previous discussions. *However, under no conditions shall the owner or their representative be allowed to bring customers or clients into the facility until the Final Certificate of Occupancy is issued.*

This is not an all-inclusive list, but a basic list of the most common of requirements

۵

For more information on Fire Safety click here



EXCELLENCE TODAY

IMPROVING TOMORROW