

THIS INSTRUMENT WAS PREPARED BY  
COLLIN WOODYARD, P.S.M.  
OF  
**BOHLER //**  
•LAND SURVEYING •CIVIL ENGINEERING •PROGRAM MANAGEMENT  
•PLANNING & LANDSCAPE ARCHITECTURE •SUSTAINABLE DESIGN  
1900 CORPORATE BLVD. NW, SUITE 101E  
BOCA RATON, FLORIDA 33431-5615 571.0280  
CERTIFICATE OF AUTHORIZATION NO. 8085

**DELRAY COMMONS BURGER KING REPLAT**  
BEING A REPLAT OF TRACT 1, DELRAY COMMONS, AS RECORD IN PLAT BOOK 85,  
PAGE 183 THROUGH 184, INCLUSIVE, PUBLIC RECORDS OF PALM BEACH COUNTY, FLORIDA, AND LYING IN  
SECTION 14, TOWNSHIP 46 SOUTH, RANGE 42 EAST, CITY OF DELRAY BEACH,  
PALM BEACH COUNTY, FLORIDA

38

**LEGEND / ABBREVIATIONS:**

- FS - FLORIDA STATUTE
- LB - LICENSED BUSINESS
- O.R.B. - OFFICIAL RECORDS BOOK
- P.B. - PLAT BOOK
- PG. - PAGE
- PLS - PROFESSIONAL LAND SURVEYOR
- PSM - PROFESSIONAL SURVEYOR AND MAPPER
- PRM - PERMANENT REFERENCE MONUMENT
- R/W - RIGHT-OF-WAY
- FDOT - FLORIDA DEPARTMENT OF TRANSPORTATION
- PBC - PALM BEACH COUNTY



**NOTES**  
**COORDINATES, BEARINGS AND DISTANCES**  
BEARINGS AND COORDINATES SHOWN HEREON ARE GRID  
FLORIDA STATE PLANE COORDINATE SYSTEM  
ZONE = FLORIDA EAST  
TRANSVERSE MERCATOR PROJECTION  
DATUM = NORTH AMERICAN DATUM OF 1983  
WITH THE 1990 ADJUSTMENT PER PALM BEACH COUNTY  
LINEAR UNIT = US SURVEY FEET  
ALL DISTANCES ARE GROUND  
SCALE FACTOR = 1.000035664  
GROUND DISTANCE X SCALE FACTOR = GRID DISTANCE

N. 773011.41 DENOTES FLORIDA STATE PLANE COORDINATES  
E. 942634.68

"NOTICE" THIS PLAT, AS RECORDED IN ITS GRAPHIC FORM,  
IS THE OFFICIAL DEPICTION OF THE SUBDIVIDED LANDS  
DESCRIBED HEREIN AND WILL IN NO CIRCUMSTANCES BE  
SUPPLANTED IN AUTHORITY BY ANY OTHER GRAPHIC OR  
DIGITAL FORM OF THE PLAT. THERE MAY BE ADDITIONAL  
RESTRICTIONS THAT ARE NOT RECORDED ON THIS PLAT  
THAT MAY BE FOUND IN THE PUBLIC RECORDS OF PALM  
BEACH COUNTY.

**SURVEYOR NOTES**

1. IN THOSE CASES WHERE EASEMENTS OR DIFFERENT TYPES CROSS OR OTHERWISE COINCIDE, DRAINAGE EASEMENTS SHALL HAVE FIRST PRIORITY, UTILITY EASEMENTS SHALL HAVE SECOND PRIORITY, ACCESS EASEMENTS SHALL HAVE THIRD PRIORITY, AND ALL OTHER EASEMENTS SHALL BE SUBORDINATE TO THESE WITH THEIR PRIORITIES BEING DETERMINED BY USE RIGHTS GRANTED.
2. BUILDING SETBACK LINE SHALL BE AS REQUIRED BY THE CITY OF DELRAY BEACH, PALM BEACH COUNTY ZONING REGULATIONS.
3. THERE SHALL BE NO TREES OR SHRUBS PLACED ON UTILITY EASEMENTS WHICH ARE PROVIDED FOR WATER AND SEWER USE OR UPON DRAINAGE EASEMENTS. LANDSCAPING ON OTHER UTILITY EASEMENTS SHALL BE ALLOWED ONLY AFTER CONSENT OF ALL UTILITY COMPANIES OCCUPYING SAME.
4. THERE MAY BE ADDITIONAL RESTRICTIONS THAT ARE NOT RECORDED ON THIS PLAT, THAT MAY BE FOUND IN THE PUBLIC RECORDS OF PALM BEACH COUNTY, FLORIDA.
5. THE CITY OF DELRAY BEACH IS HEREBY GRANTED THE RIGHT OF ACCESS FOR EMERGENCY AND MAINTENANCE PURPOSES.
6. ● PRM - PERMANENT REFERENCE MONUMENT SET 5/8" IRON ROD AND CAP STAMPED PRM LB. 8085, UNLESS OTHERWISE NOTED.
7. ALL RECORDING REFERENCES ARE RECORDED IN THE PUBLIC RECORDS OF PALM BEACH COUNTY, FLORIDA.
8. BEARINGS SHOWN HEREON ARE GRID BASED TO THE FLORIDA STATE PLANE COORDINATE SYSTEM. THE EAST LINE OF SECTION 14, TOWNSHIP 46 SOUTH, RANGE 43 EAST, PALM BEACH COUNTY, FLORIDA, BEING NORTH 00°24'32" WEST BASED ON COORDINATES PUBLISHED BY PALM BEACH COUNTY.
9. THERE SHALL BE NO BUILDINGS OR ANY KIND OF CONSTRUCTION PLACED ON WATER, SEWER OR DRAINAGE EASEMENTS. NO STRUCTURES SHALL BE PLACED WITHIN A HORIZONTAL DISTANCE OF 10 FEET FROM ANY EXISTING OR PROPOSED CITY OF DELRAY BEACH MAINTAINED WATER, SEWER OR DRAINAGE FACILITIES. CONSTRUCTION OF LANDSCAPING UPON MAINTENANCE OR MAINTENANCE ACCESS EASEMENTS MUST BE IN CONFORMANCE WITH ALL BUILDING AND ZONING CODES AND/OR ORDINANCES OF THE CITY OF DELRAY BEACH.



**SHEET 2 OF 2**

**TABULAR DATA**

LOT 1	=	37,130 SQUARE FEET OR 0.853 ACRES
LOT 2	=	275,879 SQUARE FEET OR 6.333 ACRES
TOTAL	=	313,009 SQUARE FEET OR 7.186 ACRES